

Subdivisional Lines, T 6 N R 31 E W M.

Chains	
40.60	Set basalt stone, 24 x 10 x 4, 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor.
81.20	The Cor. Land; rolling. Soil; 1st rate. Grass; good.
	Note: The S. Bdy. of Secs. 34 is 81.22 chs. in length. (See field notes of Resurvey of Exterior Bdys. of T.5 N R 31 E., N. Bdy. Sec. 3.) Nov. 14, 1874.
	N. bet. Secs. 27 & 28. Var. 22°15' E.
37.00	Ravine, course S.W.
40.00	Set basalt stone, 16 x 8 x 6, 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 21, 22, 27 & 28. Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; good. Grass; good.
	E. on random line bet. Secs. 22 & 27.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.90	Intersect N. & S. line at Cor. W. on true line.
40.45	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
56.00	Ravine, course S.W.
80.90	The Cor. Land; rolling. Soil; good.