

Subdivisional Lines, T 6 N R 31 E W M.

Chains	
	N. bet. Secs. 29 & 30.
	Var. 21°30' E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 19, 20, 29 & 30. Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; good.
	E. on random line bet. Secs. 20 & 29.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
73.52	Intersect N. & S. line, 838 lks. N. of Cor. N. 83°30' W. on true line.
37.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
74.00	The Cor. Land; rolling. Soil; good.
	W. on random line bet. Secs. 19 & 30.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.00	Intersect W. Bdy. of Tp., 96 lks. S. of Cor. S. 89°19' E. on true line.
7.00	Leave Columbia River bottom, brs. N.E. & S.W.
39.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
79.00	The Cor. Land; E. $\frac{1}{2}$, gently rolling. W. $\frac{1}{2}$, hillside, sloping to N.W. Soil; good. Grass; good.
	N. bet. Secs. 19 & 20.
	Var. 21°45' E.