

Subdivisional Lines, T 6 N R 31 E W M.

Chains	
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 17, 18, 19 & 20. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; gently rolling. Soil; good.
40.00	E. on random line bet. Secs. 17 & 20. Set temp. $\frac{1}{4}$ Sec. Cor.
73.40	Intersect N. & S. line, 902 lks. N. of Cor. N.83°00' W. on true line.
37.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions for $\frac{1}{4}$ Sec. Cor.
74.00	The Cor. Land; rolling. Soil; good.
39.85	W. on true line bet. Secs. 18 & 19. Left bank of Columbia River; set poplar post, $4\frac{1}{2}$ ft. long, 4 ins. diam.; drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to frac. Secs. 18 & 19. Land; hillside, sloping N.W. Soil; 2nd rate.
35.25	N. bet. Secs. 17 & 18. Var. 21°30' E. Intersect State Bdy. line, 568 lks. E. of Initial point, where Set basalt stone, 18 x 12 x 5, for Closing Cor. to frac. Secs. 17 & 18. Land; hillside, sloping N.W. Soil; 2nd rate.