

East Bdy., T 6 N R 32 E W M.,
 As surveyed by Odell & Lewis, U.S. Deputy Surveyors,
 Under Contract No. 110,
 Dated Feby. 7, 1865.

Chains	Commenced survey of Tp. 6 N. of Base line of R. 32 E., W.M. <p style="text-align: right;">May 10th, 1865.</p> N. bet. Rs. 32 & 33 E. in Tp. 6 N., on E. Bdy. of Sec. 36. <p style="text-align: right;">Var. 21° E.</p>
40.00	Set $\frac{1}{4}$ Sec. post, on land sloping to the NE. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 25, 36, 30 & 31. Planted stone of about 3 lbs. weight, marked & set post; dug pits & raised mound, as per instructions.
	Land; very broken. Grass; good. Soil; 2nd rate.
	N. on E. Bdy. of Sec. 25. <p style="text-align: right;">Var. 21° E.</p>
12.00	Road, course NW.
12.50	Dry branch, course NW.
40.00	Set $\frac{1}{4}$ Sec. post, in ravine, course SW. Drove charred stake; and made mound of stone, as per instructions.
60.00	Summit of hill.
80.00	Set post Cor. for Secs. 19, 30, 24 & 25, on level. Drove charred stake; dug pits & raised mound, as per instructions.
	This line passes over very broken land. Soil; 2nd rate.
	N. on E. Bdy. of Secs. 24. <p style="text-align: right;">Var. 21° E.</p>
40.00	Set $\frac{1}{4}$ Sec. post Cor., on rocky point. Drove charred stake; dug pits & made mound of stone, as per instructions.
80.00	Set post Cor. for Secs. 13, 24, 18 & 19, in depressions between ridges. Drove charred stake; dug pits & raised mound, as per instructions.
	Land; very broken. Grass; good. Soil; hardly 2nd rate.