

East Bdy., T 6 N R 32 E W M.

Chains	<p>N. on E. Bdy. of Sec. 13.</p> <p style="text-align: right;">Var. 21° E.</p> <p>39.50 Intersect Oregon Line, 8.66 chs. W. of Mile post No. 11. Set post Cor. for frac. Secs. 13 &amp; 18. Drove charred stake; dug pits &amp; raised mound, as per instructions.</p> <p>Land; broken. Grass; good. Soil; 2nd rate.</p>
<p>Subdivisional Lines, T 6 N R 32 E W M. As surveyed by Nicholas O. Walden, U.S. Deputy Surveyor, Under Contract No. 209, Dated July 6th, 1874.</p>	
<p>From the established Cor. of Secs. 35 &amp; 36 on S. Bdy. of the Tp., I run</p> <p>N. bet. Secs. 35 &amp; 36.</p> <p>40.00 Deposit basalt stone, 6 x 4 x 3, marked with a cross (x) &amp; raised mound of earth, with pits, etc., as per instruc- tions, for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>80.00 Set basalt stone, 15 x 10 x 6, 8 ins. in ground, for Cor. to Secs. 25, 26, 35 &amp; 36.</p> <p>Land; gently rolling. Soil; good. Grass; good.</p>	
<p>E. on random line bet. Secs. 25 &amp; 36.</p> <p>40.00 Set temp. <math>\frac{1}{4}</math> Sec. Cor.</p> <p>80.40 Intersect N. Bdy. of Tp., 40 lks. S. of Cor. S. 89° 33' W. on true line.</p> <p>40.20 Set basalt stone, 18 x 9 x 6, 9 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>80.40 The Cor.</p> <p>Land; rolling. Soil; good. Grass; good.</p>	