

Subdivisional Lines, T 6 N R 32 E W M.

Chains

81.20 Intersect N. & S. line, 20 lks. N. of Cor.
N.89°51' W. on true line.

40.60 Drove charred stake & raised mound of earth, with pits, etc.,
as per instructions, for $\frac{1}{2}$ Sec. Cor.

81.20 The Cor.
Land; rolling.
Soil; good.
Grass; good.

N. bet. Sees. 15 & 16.
Var.22°30'E.

40.00 Intersect Bdy. line bet. Oregon & Washington Territory, 807
lks. W. of 8 Mile Cor.
Drove charred stake & raised mound of earth, with pits, etc.,
for Closing Cor. to frac. Sees. 15 & 16.
Drove pine stake, 2 ft. long, 2 ins. sq. in E. pit.
Land; gently rolling.
Soil; good.
Grass; good.

N. bet. Sees. 32 & 33.

40.00 Drove charred stake & raised mound of earth, with pits, etc.,
as per instructions, for $\frac{1}{2}$ Sec. Cor.

80.00 Drove charred stake & raised mound of earth, with pits, etc.,
as per instructions, for Cor. to Sees. 28, 29, 32 & 33.
Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit.
Land; rolling.
Soil; 1st rate.
Grass; good.

E. on random line bet. Sees. 28 & 33.

40.00 Set temp. $\frac{1}{2}$ Sec. Cor.

80.80 Intersect N. & S. line, 12 lks. S. of the Cor.
S.89°55' W. on true line.