

Subdivisional Lines, T 6 N R 33 E W M.

Chains

E. on random line bet. Secs. 15 & 22.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

79.24 Intersect N. & S. line, 175 lks. S. of the Cor.

S. $88^{\circ}45'$ W. on true line.

39.62 Set basalt stone, 14 x 7 x 6, 7 ins. in ground, for $\frac{1}{4}$ Sec.
Cor.

79.24 The Cor.

Land; hilly.

Soil; 2nd rate.

Nov. 26th, 1874.

N. bet. Secs. 15 & 16.

Var. $21^{\circ}00'$ E.

40.00 Drove charred stake & raised mound of earth, with pits, etc.,
as per instructions, for $\frac{1}{4}$ Sec. Cor.

40.50 Intersect Bdy. line bet. Oregon & Washington Territory,
592 lks. W. of 14 Mile Cor.

Drove charred stake & raised mound of earth, with pits, etc.,
as per instructions, for Closing Cor. to fractional
Secs. 15 & 16.

Drove pine stake, 2 ft. long, 2 ins. sq. in E. pit.

Note:

Remeasured the 15th Mile on the State Bdy. line E. from
the 14th to the 15th Mile Cor. and found it to be 80.50
chs. in length.

Land; rolling., sloping to N.

Soil; 2nd rate.

N. bet. Secs. 32 & 33.

40.00 Deposited basalt stone, 10 x 8 x 6, marked $\frac{1}{4}$ and raised
mound of earth with pits, etc., as per instructions, for
 $\frac{1}{4}$ Sec. Cor.

80.00 Set basalt stone, 18 x 9 x 5, 9 ins. in ground, for Cor. to
Secs. 28, 29, 32 & 33.

Land; hilly. Soil; good.