

Subdivisional Lines, T 6 N R 33 E W M.

Chains	N. bet. Secs. 31 & 32.
33.50	Ravine, course W.
40.00	Set basalt stone, 12 x 10 x 5, 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor.
80.00	Set basalt stone, 14 x 8 x 6, 7 ins. in ground, for Cor. to Secs. 29, 30, 31 & 32.
	Land; hilly.
	Soil; 1st rate.
	E. on random line bet. Secs. 29 & 32.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.48	Intersect N. & S. line, 12 lks. S. of the Cor. S.89°55' W. on true line.
40.24	Deposited basalt stone, 8 x 4 x 3, marked with a cross & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.48	The Cor. Land; rolling. Soil; 1st rate.
	W. on random line bet. Secs. 30 & 31.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
81.96	Intersect W. Bdy. of Tp., 93 lks. S. of the Cor. S.89°20' E. on true line.
10.40	Wagon road, in ravine, course N.W.
41.96	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
81.96	The Cor. Land; hilly. Soil; good.
	Note: The S. Bdy. of Sec. 31 has a bearing S.89°11' E. and is 81.80 chs. long.