

## East Boundary, T 6 N R 34 E W M.

Chains	N. on E. Bdy. of Sec. 13.
14.10	Cross road, course W.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
48.50	Road, course W.
52.00	Intersect State line, 1365 W. of 23rd Mile post. Set Cor. for fractional Secs. 13 & 18; dug pits; drove charred stake & raised mound, as per instructions. Land; level. Soil; 2nd rate.
Subdivisional Lines, T 6 N R 34 E W M., As surveyed by Odell & Lewis, U.S. Deputy Surveyors, Under Contract No. 110, Dated Feby. 7th, 1865.	
	N. bet. Secs. 35 & 36.  Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post; dug pits & raised mound; drove charred stake; as per instructions.
80.00	Set post Cor. for Secs. 25, 26, 35 & 36. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Soil; 2nd rate.
	E. on random line bet. Secs. 25 & 36.
16.00	Dry creek, 25 lks. wide, course N.W.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
45.60	Cross ditch, fence and enter field.
58.80	Leave field.
79.28	Intersect E. & W. line, 40 lks. S. of post, from which, I run S. 89° 43' W. on true line.
39.64	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
79.28	To post Cor. Land; rolling. Soil; 2nd rate.