

Subdivisional Lines, T 6 N R 33 E W M.

Chains	Land; rolling. Grass; good. Soil; 2nd rate.
	E. on random line bet. Secs. 13 & 24.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. post.
79.47	Intersect E. Tp. line, 67 lks. S. of post, from which, I run
	S. 89° 31' W. on true line.
39.73	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
79.47	To post Cor.
	Land; gently rolling.
	Soil; 2nd rate.
	N. bet. Secs. 13 & 14.
	Var. 21° E.
.15	Spring branch, course W.
22.50	Road, course W.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
52.41	Intersect State Edge, 11.56 chs. W. of 22nd Mile post. Set post Cor. for Secs. 13 & 14. Drove charred stake; dug pits & raised mound, as per instructions.
	N. bet. Secs. 34 & 35.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
43.50	Pine creek, 25 lks. wide, course N.W.
49.00	" " " " " " N.E.
80.00	Set post Cor. for Secs. 26, 27, 34 & 35. Drove charred stake; dug pits & raised mound, as per instructions.