

Subdivisional Lines, T 6 N R 34 E W M.

Chains	<p>Land; broken, from Pine Creek N., the soil is 1st rate.; S. 2nd rate.</p> <hr/> <p>E. on random bet. Secs. 26 &amp; 35.</p> <p>12.75 Pine Creek, course N.</p> <p>40.00 Set temp. <math>\frac{1}{4}</math> Sec. post.</p> <p>79.75 Intersect N. &amp; S. line, 55 lks. N. of post, from which I run N.89°35' W. on true line.</p> <p>39.87 Set <math>\frac{1}{4}</math> Sec. post Cor. Drove charred stake; dug pits &amp; raised mound, as per instructions.</p> <p>79.75 To post Cor. Land; gently rolling. Soil; E. to the crossing of Pine Creek, 1st rate and under cultivation, Pine Creek forming the inclosure on the S. and E.</p> <hr/> <p>N. bet. Secs. 26 &amp; 27.</p> <p style="text-align: right;">Var.21° E.</p> <p>40.00 Set <math>\frac{1}{4}</math> Sec. post Cor. Drove charred stake; dug pits &amp; raised mound, as per instructions.</p> <p>46.50 Pine Creek, course N.W.</p> <p>80.00 Set post Cor. for Secs. 22, 23, 26 &amp; 27. Drove charred stake; dug pits &amp; raised mound, as per instructions. Land; gently rolling. Soil; to Pine Creek, 1st rate, thence 2nd rate,</p> <hr/> <p>E. on random bet. Secs. 23 &amp; 26.</p> <p>40.00 Set temp. <math>\frac{1}{4}</math> Sec. post Cor.</p> <p>80.25 Intersect N. &amp; S. line, 30 lks. N. of post, from which, I run N.89°47' W. on true line.</p> <p>40.12 Set <math>\frac{1}{4}</math> Sec. post. Drove charred stake; dug pits &amp; raised mound, as per instructions.</p>
--------	---