

## Subdivisional Lines, T 6 N R 34 E W M.

Chains	
80.25	To post Cor. Land; gently rolling. Soil; 2nd rate.
<hr/>	
	N. bet. Secs. 22 & 23. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits and raised mound, as per instructions.
49.00	Creek, 10 lks. wide, course N.W.
52.15	Road, course N.W.
80.00	Set post Cor. for Secs. 14, 15, 22 & 23. Drove charred stake; dug pits & raised mound, as per instructions. Land; gently rolling. Soil; 2nd rate.
<hr/>	
	E. on random bet. Secs. 14 & 23.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. post.
79.75	Intersect N. & S. line, 8 lks. S. of post, from which, I run S. 89° 57' W. on true line.
39.87	Set $\frac{1}{4}$ Sec. Cor. post. Drove charred stake; dug pits & raised mound, as per instructions.
79.75	To post Cor. Land; gently rolling. Soil; good 2nd rate. Grass; good.
<hr/>	
	N. bet. Secs. 14 & 15. Var. 21° E.
9.35	Road, course N.W.
40.00	Set post Cor. for $\frac{1}{4}$ Sec. Drove charred stake; dug pits & raised mound, as per instructions.
46.00	Spring granch, course N.W.
52.10	To State Line, 9.78 chs. W. of 21st Mile post. Set post Cor.