

Subdivisional Lines, T 6 N R 34 E W M.

Chains	
	mound, as per instructions.
80.00	Set post Cor. for Secs. 20, 21, 28 & 29. Drove charred stake dug pits & raised mound, as per instructions. Land; rolling. Grass; good. Soil; 2nd rate.
	E. on random bet. Secs. 21 & 28.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.17	Intersect N. & S. line at post, from which I run W. on true line.
40.08	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.17	To, post Cor. Land; rolling. Soil; 2nd rate.
	N. bet. Secs. 20 & 21.
22.50	Trail, course W. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Post Cor. for Secs. 16, 17, 20 & 21. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Grass; good. Soil; 2nd rate.
	E. on random bet. Secs. 16 & 21.
7.60	Read, course N.W.
9.76	Pine Creek, course N.W.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.25	Intersect N. & S. line, 80 lks. S. of post, from which, I run S.89°47' W. on true line.