

Subdivisional Lines, T 6 N R 35 E W M.

Chains

80.05 To post Cor.
Land; level.
Soil; in field, 1st rate - balance stony.
Some cotton wood, alder & birch timber along the streams,
but of small growth.

N. bet. Secs. 25 & 26. H
Var. 21° E.

32.20 Enter field, course of fence, N.W.

40.00 Set $\frac{1}{2}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.

49.00 Cross partition fence, course N.E.

79.00 Spring branch, 10 lks. wide, course N.E.

80.00 Set post Cor. for Secs. 23, 24, 25 & 26. Drove charred stake; dug pits & raised mound, as per instructions.
Land; level.
Soil; 1st rate.
Some willow & alder along spring branch.

E. on random bet. Secs. 24 & 25. H.

1.50 Spring branch, course N.E.

40.00 Set $\frac{1}{2}$ Sec. post temp. Cor.

45.00 Road, course N.

62.50 Creek, 60 lks. wide, course N.

79.78 Intersect E. Tp. line, 52 lks. N. of post, from which, I run
N. 89° 38' W. on true line.

39.89 Set $\frac{1}{2}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.

79.78 To post Cor.
Land; level.
Some timber along the bank of stream, consisting of cotton-wood, alder & birch, willow undergrowth.
Soil; 1st rate.