

## Subdivisional Lines, T 6 N R 35 E W M.

Chains	A
	N. bet. Secs. 23 & 24.
	Var. 21° E.
40.00	Set $\frac{1}{2}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
59.00	Creek, 15 lks. wide, course N.W.
62.00	Summit of bank.
80.00	Set post Cor. for Secs. 13, 14, 23 & 24. Drove charred stake; dug pits & raised mound, as per instructions.
	Land; level to bank.
	Soil; 1st rate, on bank 3rd rate.
<hr/>	
	E. on random bet. Secs. 13 & 24.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
47.00	Descend bank.
55.00	Creek, 40 lks. wide, course N.
55.00	" 25 " " " "
57.00	Leave creek bottom.
79.91	Intersect E. Tp. line, 21 lks. N. of post Cor.; from which, I run N. 89° 51' W. on true line.
39.95	Set $\frac{1}{2}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
79.91	To post Cor. Land; rolling. Soil; on bank of creek, hardly 2nd rate, along creek, 1st rate.
<hr/>	
	N. bet. Secs. 13 & 14.
	Var. 21° E.
40.00	Set $\frac{1}{2}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
49.00	Spring branch, course N.W.
53.50	Intersect N. State Line, 17.30 W. of post on said Line, marked 28 M.
	Set post Cor. for fractional Secs. 13 & 14. Drove charred