

Subdivisional Lines, T 6 N R 35 E W M.

Chains	
64.55	Creek, 45 lks. wide, course N.
70.00	Same creek, course E. of N.
79.10	" " " W. of N.
80.00	Set Secs. 22, 23, 26 & 27 Cor. post. Drove charred stake; from which, A red willow, 3 ins. diam., brs. N.49°W., 15 lks. dist. A birch, 7 ins. diam., brs. S.66°30'E., 52 lks. dist. A cottonwood, 10 ins. diam., brs. S.57°W., 30 lks. dist. This line passes over level land. Soil; 1st rate. Some timber along creek, cottonwood, alder & birch. Willow undergrowth.
	E. on random bet. Secs. 23 & 26.
4.50	Same creek as above, course E.
6.50	Turns to N.E.
7.00	N. Forā's house brs. N. 1.00
8.00	Spring branch, course N.
30.00	Enter brush, course N.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
41.87	Road, course N.
46.52	Creek, 10 lks. wide, course N.
49.00	House brs. N. 2.00 chs.
79.50	Intersect N. & S. line, 15 lks. N. of post Cor., from which I run N.89°54'W., on true line.
39.75	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions, from which A willow, 8 ins. diam., brs. N. 81°30'W., 58 lks. dist.
79.50	To post Cor. Land; level. Soil; 1st rate.
	N. bet. Secs. 22 & 23. Var. 21°E.