

Subdivisional Lines, T 6 N R 35 E W M.

Chains

12.00 Walla Walla River, as above, course N.E.
 13.15 Same stream, course W. of N.
 25.00 Small creek, 4 lks. wide, course N.W.
 36.00 House brs. W., 2;00 chs.
 40.00 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
 80.00 Set post Cor. for Secs. 14, 15, 22 & 23; drove charred stake; dug pits & raised mound, as per instructions.
 Land; level, excepting the last 20 chs., which passes over barren ridge.
 Soil; 1st rate.
 Timber along creek, as above stated.

E. on random bet. Secs. 14 & 23.
 20.00 House brs. S., 50 lks.
 25.70 Creek, 30 lks. wide, course N.W.
 40.00 Set temp. $\frac{1}{4}$ Sec. post.
 66.94 Creek, 20 lks. wide, course N.
 73.50 Top of bank.
 79.70 Intersect N. & S. line, 13 lks. N. of post, from which,
 I run
 N.89°54'W. on true line.
 39.85 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
 79.70 To post Cor.
 This line passes over barren land, the first 20 chs., then 1st rate land to bank, then barren.

N. bet. Secs. 14 & 15.

Var.21°E.

12.00 Creek, 6 lks. wide, course N.W.
 40.00 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
 53.00 Intersect State Bdy., 17.20 W. of Bdy. Monument post marked