

Subdivisional Lines, T 6 N R 35 E W M.

Chains	
	N. bet. Secs. 16 & 17. Var. 21°E.
15.18	Ditch fence.
17.15	Creek, 10 lks. wide, course W.
32.13	Leave field, ditch fence.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
53.10	To N. Bdy. of State, 13.50 chs. W. of 25th Mile post. Set post Cor. for fractional Secs. 16 & 17. Drove charred stake; dug pits & raised mound, as per instructions. Land; gently rolling. Grass; good. Soil; 2nd rate.
	N. bet. Secs. 31 & 32.
10.80	Dry creek, 25 lks. wide, course N.W.
40.00	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound.
80.00	Set post Cor. for Secs. 29, 30, 31 & 32. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Grass; good. Soil; 2nd rate.
	E. on random bet. Secs. 29 & 32.
12.22	Spring branch, course N.W.
22.00	" " " "
27.00	" " " "
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.54	Intersect N. & S. line, 50 lks. N. of post, from which, I run N. 89° 39' W. on true line.
39.77	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits and raised mound, as per instructions.
79.54	To post Cor. Land; gently rolling. Grass; good. Soil; 2nd rate.