

Exterior Lines, T 6 N R 36 E W M.,
 As surveyed by Odell & Lewis, U.S. Deputy Surveyors,
 Under Contract No. 110,
 Dated Feb. 7, 1865.

Chains

N. on E. Bdy. of Sec. 36, T 6 N R 36 E.

Var. 21° E.

14.70 Creek, 6 lks. wide, course N.W.

40.00 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions,

80.00 Set post Cor. for Secs. 25, 26, 30 & 31. Drove charred stake; dug pits & raised mound, as per instructions.
 Land; broken.

Soil; good 2nd rate.

Grass; good.

N. on E. Bdy. of Secs. 25.

Var. 21° E.

39.50 Mt. road, course E.

40.00 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions,

80.00 Set post Cor. for Secs. 24, 25, 19 & 30. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken.

Grass; good.

Soil; good 2nd rate.

N. on E. Bdy. of Sec. 24.

Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 13, 24, 18 & 19. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken.

Grass; good.

Soil; good 2nd rate.

N. on E. Bdy. of Sec. 13.

Var. 21° E.

24.50 Creek, 15 lks. wide, course N.W.

38.50 Road, course N.W.