

Subdivisional Lines, T 6 N R 36 E W M.

Chains	mound, as per instructions.
80.00	Set post Cor. for Secs. 23, 24, 25 & 26, at ft. of hill, sloping to E. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Grass; good. Soil; 2nd rate.
	E. on random bet. Secs. 24 & 25.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.18	Intersect N. & S. Tp. line, 28 lks. N. of post, from which I run N.89°48'W. on true line.
40.09	Set $\frac{1}{4}$ Sec. post at ft. of hill, facing E. Drove charred stake; dug pits & raised mound, as per instructions.
80.18	To post Cor. Land; rolling. Grass; good. Soil; 2nd rate.
	N. bet. Secs. 23 & 24.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions. Var.21°E.
80.00	Set post Cor. for Secs. 13, 14, 23 & 24. Drove charred stake; dug pits & raised mound, as per instructions. Land; gently rolling. Grass; good. Soil; 2nd rate.
	E. on random bet. Secs. 13 & 24.
	Var.21°E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.89	Intersect N. & S. Tp. line, at post, from which, I run W. on true line.
39.94	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
79.89	To post Cor. Land; rolling gently. Grass; good. Soil; 2nd rate.