

Subdivisional Lines, T 6 N R 36 E W M.

Chains	mound, as per instructions.
80.19	To post Cor. Land; rolling. Grass; good. Soil; 2nd rate.
N. bet. Secs. 14 & 15.	
Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake.
52.20	Intersect State Bdy. Line, 16 chs. & 55 lks. W. of Mile post, No. 33. Set post Cor. for fractional Secs. 14 & 15. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Grass; good. Soil; 2nd rate.
N. bet. Secs. 33 & 34.	
Var. 21° E.	
30.00	Road, course W. of N.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 27, 28, 33 & 34. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Grass; good. Soil; 2nd rate.
E. on random bet. Secs. 27 & 34.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.94	Intersect N. & S. line, 12 lks. S. of post, from which, I run S. 89° 55' W. on true line.
39.97	Dug pits & raised mound, as per instructions.