

Subdivisional Lines, T 6 N R 36 E W M.

Chains	
	E. on random bet. Secs. 28 & 33.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.28	Intersect N. & S. line, at post, from which, I run W. on true line.
40.14	Set $\frac{1}{4}$ Sec. post; dug pits & raised mound; drove charred stake; as per instructions.
68.00	Road, course W. of N.
80.28	To post Cor. Land; gently rolling. Grass; good. Soil; 2nd rate.
N. bet. Secs. 28 & 29.	
	Var. 21°E.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 20, 21, 28 & 29. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Grass; good. Soil; 2nd rate.
E. on random bet. Secs. 21 & 28.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.00	Intersect N. & S. line, 25 lks. N. of post, from which, I run N. 89° 49' W. on true line.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
47.50	Road, course W. of N.
80.00	To post Cor. Land; gently rolling. Soil; 2nd rate.