

Subdivisional Lines, T 6 N R 36 E W M.

Chains

N. bet. Secs. 31 & 32.

Var. 21° E.

40.00 Set  $\frac{1}{4}$  Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 29, 30, 31 & 32. Drove charred stake; dug pits & raised mound, as per instructions.

Land; rolling gently.

Grass; good.

Soil; 2nd rate.

E. on random bet. Secs. 29 & 32.

40.00 Set temp.  $\frac{1}{4}$  Sec. post.

79.78 Intersect N. & S. line, 32 lks. N. of post, from which, I run

N. 89° 46' W. on true line.

39.89 Set  $\frac{1}{4}$  Sec. post; dug pits; drove charred stake & raised mound, as per instructions.

79.78 To post Cor.

Land; gently rolling.

Grass; good.

Soil; 2nd rate.

W. on random bet. Secs. 30 & 31.

40.00 Set temp.  $\frac{1}{4}$  Sec. post.

79.75 Intersect N. & S. Tp. line, 18 lks. N. of post, from which, I run

N. 89° 52' E. on true line.

39.75 Set  $\frac{1}{4}$  Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

65.25 Creek, course N.W.

79.75 To post Cor.

Land; gently rolling.

Grass; good.

Soil; 2nd rate.