

Exterior Lines, T 6 N R 37 E W M.

Chains	and the difficulty of getting to the work, prevented our return.
<p>Field Notes to Complete Exterior Lines of T 6 N R 37 E W M. As surveyed by George Williams, U.S. Deputy Surveyor, Under Contract No. 176, Dated July 20, 1872.</p>	
<p>Begin at the established Cor. for Secs. 19, 24, 25 & 30, on the Range Line bet. Rs. 27 & 28 E., T 6 N. Witness trees standing and agree with description, furnished me by the Office.</p>	
<p>From which Cor., I run N. bet. Secs. 19 & 24.</p>	
Var. 22 $\frac{1}{2}$ ° E.	
Descend.	
1.50	Leave small timber; enter prairie.
6.00	Enter timber.
40.00	Set post for $\frac{1}{4}$ Sec. Cor. on side hill, facing W., from which
A fir tree, 10 ins. diam., brs. N. 20° W., 18 lks. dist.	
A fir tree, 15 ins. diam., brs. N. 16° E., 20 lks. dist.	
72.44	Bottom of gulch, 400 ft.; a creek, 5 lks. wide, falls N.E.
Ascend.	
73.00	Leave timber.
80.00	Set post & mark a basalt rock, 12 x 12 x 9, in mound of stone in side hill, facing S., for the Cor. to Secs. 13, 18, 19 & 24.
Land; mountainous, valuable only for its scattering timber of pine, fir & tamarack.	
N. bet. Secs. 13 & 18.	
Var. 22° E.	
10.30	Enter timber.
16.30	Ridge, 150 ft. falls E.
23.80	Bottom of gulch, 300 ft., falls E.
Ascend.	
34.0	