

Subdivisional Lines, T 6 N R 37 E W M.

Chains	E. on random bet. Secs. 25 & 36.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.18	Intersect E. Bdy. of Tp., 27 lks. N. of Cor. for Secs. 25, 30, 31 & 36, from which Cor., I run N.89°48'W. on true line bet. Secs. 25 & 36.
19.18	Timber road, N.W. & S.E.
24.60	Spring branch, 50 lks. W., falls N.W.
40.09	Set post for $\frac{1}{4}$ Sec. Cor., from which, A white fir, 8 ins. diam., brs. N.10°W., 29 lks. dist. A tamarack, 14 ins. diam., brs. S.42°W., 26 lks. dist.
51.70	Spring branch, 1 lk. wide, falls N.W.
54.80	Ascend.
56.80	Timber road, N.W. & S.E.
80.18	To Cor.
<hr/>	
	N. bet. Secs. 25 & 26. Var. 21 $\frac{1}{2}$ °E.
25.70	Spring branch, 10 lks. wide, falls N.70°W.
26.20	Timber road. Ascend.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., from which A tamarack, 12 ins. diam., brs. N.10°W., 65 lks. dist. A fir, 8 ins. diam., brs. S.20°E., 20 lks. dist.
68.50	Ridge & road.
77.50	Cross gulch and ascend.
80.00	Set post for Cor. to Secs. 23, 24, 25 & 26. A white fir, 8 ins. diam., brs. S.26°E., 11 lks. dist. A white fir, 6 ins. diam., brs. S.45°W., 12 lks. dist. A fir stump, 10 ins. diam., brs. N.27°W., 35 lks. dist. Land; hilly. Timber; pine, fir & tamarack.
	Oct. 17, 1872.
<hr/>	