

Subdivisional Lines, T 6 N R 37 E W M.

Chains	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.60	Intersect N. & S. line, 57 lks. N. of the Cor. to Secs. 13, 14, 23 & 24, from which Cor., I run N.89°36'W. on true line bet. Secs. 14 & 23.
40.30	Set post for $\frac{1}{4}$ Sec. Cor., from which A tamarack, 20 ins. diam., brs. N.50°E., 19 lks. dist. A fir, 8 ins. diam., brs. S.75°E., 39 lks. dist.
54.30	Leave timber.
80.60	The Cor. for Secs. 14, 15, 22 & 23. Land; hilly.
	N. bet. Secs. 14 & 15. Var. 21°E.
37.00	Ascend summit of ridge, 500 ft.
40.00	Set stake, mound & pits for $\frac{1}{4}$ Sec. Cor.
51.75	Intersect N. Bdy. of State, 16.45 chs. W. of 39 M. post. Set rock, 6 x 7 x 18, for the Cor. of fractional Secs. 14 and 15. Land; mountainous. Good bunchgrass. Timber; pine & fir. Oct. 21, 1872.
	N. bet. Secs. 33 & 34. Var. 21 $\frac{1}{2}$ °E.
6.50	Cross ridge & descend steep hill.
40.00	Set post & rock in mound of rock for $\frac{1}{4}$ Sec. Cor.
51.50	Road, E. & W. Ascend.
72.50	Cross ridge.
80.00	Set post & stone mound & pits, for the Cor. of Secs. 27, 28, 33 & 34. Land; mountainous. ? Bunch grass: good.