

## Subdivisional Lines, T 6 N R 37 E W M.

Chains	E. on random line bet. Secs. 27 & 34.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.70	Intersect N. & S. line, 46 S. of Cor. for Secs. 26, 27, 34 & 35, from this Cor. I run S.89°40'W. on a true line bet. Secs. 27 & 34.
39.85	Set post for $\frac{1}{4}$ Sec. Cor.; mound, rock on hillside, facing S. Descend.
79.70	The Cor. of Secs. 27, 28, 33 & 34. Land; hilly. No timber. Grass; good.
<hr/>	
	N. bet. Secs. 27 & 28. Var. 21 $\frac{1}{2}$ °E.
6.25	Cross gulch & ascend.
40.00	Set stone, 12 x 13 x 24, mound of stone for $\frac{1}{4}$ Sec. Cor.
58.50	Timber road.
59.50	Summit of ridge. Descend.
80.00	Sett post & mark stone & pits for the Cor. to Secs. 21, 22, 27 & 28. Land; hilly. No timber. Grass; good.
<hr/>	
	E. on random line bet. Secs. 22 & 27.
40.00	Set post for $\frac{1}{4}$ Sec. Cor.
80.30	Intersect N. & S. line, 37 lks. N. of Cor., for Secs. 22, 23, 26 & 27, from which I run N.89°44'W. on true line bet. Secs. 22 & 27.
40.15	Set post & stone, 18 x 18 x 36, mound of stone, for $\frac{1}{4}$ Sec. Cor. A cherry bush S. side of mound.
73.50	Road, S.70°E.
78.00	Bottom of gulch. Ascend.