

Chains

Subdivisional Lines, T 6 N R 37 E W M.

80.30	The Cor. to Secs. 21, 22, 27 & 28. Land; hilly. No timber. Good grass.
	N. bet. Secs. 21 & 22. Var. $21\frac{1}{2}^{\circ}$ E.
4.25	Foot of hill road, E. & W.
5.00	Spring branch, 3 lks. wide, runs N.W. Ascend.
40.00	Set post & stone, 4 x 8 x 12, mound of stone & pits for $\frac{1}{4}$ Sec. Cor.
52.00	Ridge & descend.
80.00	Set stone, 10 x 15 x 30, pits for Cor. to Secs. 15, 16, 21 and 22. Land; very hilly. Grass; good.
	E. on random line bet. Secs. 15 & 22.
40.00	Set stone for temp. $\frac{1}{4}$ Sec. Cor.
79.78	Intersect N. & S. line, 27 lks. N. of the Cor. for Secs. 14, 15, 22 & 23, from this Cor., I run N. $89^{\circ}48'$ W. on true line bet. Secs. 15 & 22.
39.89	Set stone, 14 x 15 x 20 on steep side hill, facing N. for $\frac{1}{4}$ Sec. Cor.
59.89	Summit of ridge. Descend.
77.84	Road, N.W. & S.E. Descend.
79.78	The Cor. for Secs. 15, 16, 21 & 22. Land; hilly. No timber. Grass; good.
	N. bet. Secs. 15 & 16. Var. $21\frac{1}{2}^{\circ}$ E.
7.00	Summit of ridge; descend, falls N.W.
21.00	Road, E. & W.
40.00	Set stone, 12 x 18 x 36, for $\frac{1}{4}$ Sec. Cor.
52.13	Intersect N. Bdy. of State, 16.86 chs. W. of post, 38 M. I