

Subdivisional Lines, T 6 N R 37 E W M.

Chains	<p>Set stone, 6 x 9 x 13 for the Cor. to fractional Secs. 15 and 16.</p> <p>Land; hilly.</p> <p>Good bunch grass.</p> <p style="text-align: right;">Oct. 22, 1872.</p>
	<p>N. bet. Secs. 32 & 33.</p> <p>Ascend hill. Var. 21½° E.</p> <p>20.00 Cross timber road, N.W.</p> <p>30.00 Cross spur & descend.</p> <p>Enter timber.</p> <p>36.00 Cross gulch.</p> <p>Leave timber.</p> <p>40.00 Set post in mound of stone, for ¼ Sec. Cor.</p> <p>47.00 N. Fork of Cottonwood Creek, 10 lks. wide,</p> <p>Ascend.</p> <p>80.00 Set stone, 15 x 17 x 24, mound & pits, for Cor. to Secs. 28, 29, 32 & 33.</p> <p>Land; hilly.</p> <p>Timber; pine & fir.</p>
	<p>E. on random line bet. Secs. 28 & 33.</p> <p>40.00 Set stone for temp. ¼ Sec. Cor.</p> <p>79.70 Intersect N. & S. line, 34 lks. N. of Cor. for Secs. 27, 28, 33 & 34, from which I run</p> <p>N. 89° 45' W. on true line bet. Secs. 28 & 33.</p> <p>9.70 Gulch, 300 ft.</p> <p>Ascend.</p> <p>39.85 Set stone, 5 x 8 x 12, mound & pits, for ¼ Sec. Cor.</p> <p>52.00 Cross gulch.</p> <p>70.70 Cross ridge.</p> <p>Descend.</p> <p>79.70 The Cor. for Secs. 28, 29, 32 & 33.</p> <p>Land; mountainous. No timber.</p> <p>Good grass of the bunch variety.</p>