

## Subdivisional Lines, T 6 N R 37 E W M.

Chains	E. on random bet. Secs. 29 & 32.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.30	Intersect N. & S. line, 56 lks. S. of Cor. for Secs. 28, 29, 31 & 32, from which Cor., I run S.89°36'W. on true line bet. Secs. 29 & 32.
40.15	Set post; mark stone; mound & pits, for $\frac{1}{4}$ Sec. Cor.
62.15	Cross ridge.
68.00	Road to timber.
71.20	Cottonwood Creek, 15 lks. falls W.
80.30	The Cor. for Secs. 29, 30, 31 & 32. Land; 2nd rate. No timber. Good grass.
	W. on random line bet. Secs. 30 & 31.
40.00	Set stone for temp. $\frac{1}{4}$ Sec. Cor.
80.42	Intersect W. Bdy. of Tp., 44 lks. W. of Cor. for Secs. 25, 30, 31 & 36, from which Cor., I run N.89°41'E. on true line bet. Secs. 30 & 31.
40.21	Set post, mound & pits for $\frac{1}{4}$ Sec. Cor.
41.21	Old road, N. S.
53.12	Top of hill. Descend.
80.42	The Cor. for Secs. 29, 30, 31 & 32. Land; hilly, 2nd rate. Good grass.
	N. bet. Secs. 29 & 30. Var. 21°E.
1.00	Cross fence, enter field.
4.00	Bottom, enter young orchard.
7.40	Creek, 12 lks. wide, falls N.W.
8.00	Leave bottom. Ascend.
23.00	Cross road.