

Subdivisional Lines. T & N R 37 E W M.

Chains

28.00 Spring branch, 1 lk. wide, flows W.
 40.00 Set post, marked stone, mound & pits, for $\frac{1}{4}$ Sec. Cor.
 80.00 Set stone, 8 x 10 x 15, in mound & pits, for Cor. to Secs.
 19, 20, 29 & 30.

2nd rate soil.

Good grass.

No timber.

E. on random bet. Secs. 20 & 29.

40.00 Set stone for temp. $\frac{1}{4}$ Sec. Cor.
 79.70 Intersect N. & S. line, 31 lks. of the Cor. for Secs. 20,
 21, 28 & 29, from this Cor., I run

S.89°47'W. on true line bet. Secs. 20 & 29.

39.85 Set stone, 4 x 6 x 15, mound & pits, for $\frac{1}{4}$ Sec. Cor.

45.10 Cross ridge.

59.70 Cross gulch.

79.70 The Cor. to Secs. 19, 20, 29 & 30.

Soil; 2nd rate.

Good grass. No timber.

W. on random bet. Secs. 19 & 30.

40.00 Set stone for temp. $\frac{1}{4}$ Sec. Cor.

79.95 Intersect W. Bdy. of Tp., 67 lks. S. of the mound Cor. for
 Secs. 19, 24, 25 & 30, (post gone), from this Cor., I run

S.89°31'E., on true line bet. Secs. 19 & 30.

17.45 Cross fence.

39.95 Set post, marked stone, mound & pits, for $\frac{1}{4}$ Sec. Cor.

42.00 Mr. Henry's house, S.150 lks. dist.

44.00 Cottonwood Creek, 13 lks. wide.

60.95 Leave field, cross fence.

79.95 The Cor. for Secs. 19, 20, 29 & 30.

Soil; 2nd rate.

No timber.

Good grass.