

Subdivisional Lines, T 6 N R 37 E W M.

Chains

N. bet. Secs. 19 & 20.

Var. $21\frac{1}{2}^{\circ}$ E.

10.10.00 Cross ridge.
 40.00 Set stone, mound & pits, for $\frac{1}{4}$ Sec. Cor.
 45.00 Cross road to timber.
 46.00 Cross fence, enter field.
 77.50 Cross road to timber.
 78.75 Irrigating ditch.
 80.00 Set stone, 8 x 16 x 20, for Cor. to Secs. 17, 18, 19 & 20.
 Soil; 2nd rate.
 No timber.
 Good grass.

E. on random bet. Secs. 17 & 20.

40.00 Set stone for temp. $\frac{1}{4}$ Sec. Cor.
 79.87 Intersect N. & S., 35 lks. W. of Cor. for Secs. 16, 17, 20
 and 21, from which Cor., I run
 N. $89^{\circ}45'$ W. on true line bet. Secs. 17 & 20.
 6.87 Cross ridge.
 39.93 Set stone, 6 x 8 x 12, mound of stone, for $\frac{1}{4}$ Sec. Cor.
 51.70 Irrigating ditch.
 Ascend.
 72.12 Cross creek, 18 lks. wide.
 74.77 Cross creek, leave bottom.
 Ascend.
 79.87 The Cor. for Secs. 17, 18, 19 & 20.
 Soil; 2nd rate.
 Small timber along creek.

W. on random line bet. Secs. 18 & 19.

~~40.00~~ Set post for temp. $\frac{1}{4}$ Sec. Cor.
 79.50 Intersect Tp. line at the Cor. for Secs. 13, 18, 19 & 24,
 from this Cor., I run
 E. on true line bet. Secs. 18 & 19.
 5.25 Cross fence. Descend.