

E. Bdy. of T 6 N R 38 E., W.M.

Chains		Feet
47.00	Ridge, 400 ft., fall N.W.	
56.50	Bottom of gulch, falls N. 60° W., 200 ft.	
56.75	Creek, 15 lks. wide, flows N 60° W.	
	Ascend	
80.00	Set post from which	
	A fir tree, 10 ins. diam. brs. N. 30° E., 18 lks.	
	A fir, tree, 17 ins. diam. brs. N. 42° W., 76 lks.	
	A fir, 12 ins. diam. brs. S. 31° E., 24 lks.	
	A fir, 12 ins. diam. brs. S. 29° W., 37 lks.	
	For the Cor. of Secs. 19, 30, 24 & 35	
	Land; hilly, 2nd rate	
	Timber; pine, fir, tamarack	
	N. on E. Bdy. Sec. 13	
	Var. 12½° E	
6.00	Ridge, fall N. 37° W., 300 Ft.	
18.00	Bottom of a creek, 13 lks. wide, fall N. 50° W.; a prong	
	of Mill Creek; Ascend	
40.00	Set post for ¼ Sec. Cor., from which	
	A birch, 8 ins. diam. brs. N. 76° W., 46 lks. dist.	
	A fir, 9 ins. diam. brs. S. 38° E., 29 lks. dist.	
52.20	Intersect the State Bdy. 16.80 Chs. W. of the 47 mile Cor.	
	I set stone, 28 x 21 x 15 ins. in mound of stone for	
	Closing Cor. to Fractional Tp. 6 N R 38 & 39 E.	
	Land; mountainous	
	Timber, fir, tamarack and pine	
	Complete Oct. 2nd, 1872.	
	Resurvey of the W. Bdy. of T 6 N., R 39 E., W.M.	
	As surveyed by Otis. O Gould, U.S. Transitman	
	Under special instructions, group # 135, Dated April 11,	
	1929.	
	Re "Reestablishment of the surveys excuted by George Williams,	
	U.S. Deputy Surveyor, in 1872.	
	Random line.	
	I commence the retracement at the old cor. of Tps. 6 N.,	
	Rs. 38 and 39 E.	
	North, retracing bet. secs. 31 & 36.	