

Retracement of W. Bdy. of T 6 N R 39 E., W.M.

Chains		Feet																					
40.00	Find no trace of the $\frac{1}{4}$ sec. cor. Set temp.																						
80.00	Find no trace of the cor. of secs. 25, 30, 31, and 36. Set temp.																						
	North, retracing bet. secs. 25 and 30.																						
40.00	Find no trace of the $\frac{1}{4}$ sec. cor. Set temp.																						
80.00	Find no trace of the cor. of secs. 19, 24, 25, and 30. Set temp.																						
	North, retracing bet. secs. 19 & 24.																						
40.00	Find no trace of the $\frac{1}{4}$ Sec. Cor. Set temp.																						
80.00	Find no trace of the cor. of secs. 13, 18, 19 & 24. Set temp.																						
	North, retracing bet. secs. 13 & 18.																						
40.00	Find no trace of the $\frac{1}{4}$ sec. cor. Set temp.																						
43.97	Intersect the Oregon and Washington bdy. Find no trace of the old closing cor. of Tps. 6 N., Rs. 38 & 39 E.																						
	From this point the proportionate point for the closing cor. of Tps. 6 N., R 38 & 39 E., bears N. 89°49' W., 21.11 chs. dist.																						
	The line bet. the old cor. of Tps. 6 N., Rs. 38 & 39 E., and the proportionate point for the closing cor. of Tps. 6 N., Rs. 38 & 39 E., is therefore N. 4° 15' W., 284.82 chs. The proportionate length of the E. bdys. of secs. 36, 25, 24 is 77.98 chs., and the proportionate length of the E. bdy. of sec. 13 is 50.88 chs.																						
	-----																						
	True line.																						
	Thence from the cor. of T 6 N., R. 39 E. only., herein- before described.																						
	N. on the W. Bdy. of sec. 31.																						
1.95	The old Tp. cor. of Tps. 6 N., Rs. 38 & 39 E., which is determined from traces of old rotted stake and evidence of original mound and pits.																						
	This cor. will hereafter refer to T 6 N R 38 E., and T. 5 N., R. 39 E.																						
	At true point for cor.																						
	Set an iron post, 3 ft. long, 3 ins. diam., 27 ins. in the ground, for cor. of T 6 N., R 38 E., and T 5 N., R. 39 E., with brass cap marked.																						
	<table border="0"> <tr><td>T6N</td><td> </td><td></td></tr> <tr><td>R38E</td><td> </td><td></td></tr> <tr><td>S36</td><td> </td><td>T6N</td></tr> <tr><td>S 6</td><td> </td><td>R39E</td></tr> <tr><td></td><td> </td><td>S31</td></tr> <tr><td>T5N</td><td> </td><td></td></tr> <tr><td>R39E</td><td> </td><td></td></tr> </table>	T6N			R38E			S36		T6N	S 6		R39E			S31	T5N			R39E			
T6N																							
R38E																							
S36		T6N																					
S 6		R39E																					
		S31																					
T5N																							
R39E																							
	1932																						
	from which																						
	A spruce, 9 ins. diam., brs. N. 45° W., 18 lks. dist. marked T 6 N R 38 E S 36 B T.																						