

## Resurvey of the W. Bdy. of T 6 N R 39 E.

Chains		Feet										
	<p>Set an iron post, 3 ft. long, 2 ins. diam., 18 ins. in the ground to solid rock, and in a mound of stone to top, for cor. of secs. 24 and 25 only, with brass cap marked</p> <div style="text-align: center;"> <table border="0"> <tr><td>T6N</td><td>T6N</td></tr> <tr><td>S24</td><td>R</td></tr> <tr><td>S25</td><td>R39E</td></tr> <tr><td>R38E</td><td>S30</td></tr> <tr><td colspan="2">1932</td></tr> </table> </div> <p style="text-align: right;">from which</p> <p>A fir, 10 ins. diam., brs. S. 48° W., 15 lks. dist. marked T 6 N R 38 E S 25 B T.</p> <p>A pine, 30 ins. diam., brs. N. 80° W., 19 lks. dist., marked T 6 N R 38 E S 24 B T.</p>	T6N	T6N	S24	R	S25	R39E	R38E	S30	1932		
T6N	T6N											
S24	R											
S25	R39E											
R38E	S30											
1932												
78.45	Ridge, brs. E. and W.; desc. 60 ft. over N. slope.											
80.19	Point for the closing cor. of secs. 19 and 30, determined as hereinafter set forth.											
	<p>Land; mountainous. Soil; sandy loam, rocky; 3rd rate. Timber; fir, pine, spruce and tamarack. Undergrowth, huckleberry, alder, vinemaple, willow, salal, Oregon grape, cherry, mountain laurel.</p>											
	<p>N. 4° 15' W., resurveying the W. bdy. of sec. 19. Desc. 170 ft. over NW. slope, through timber and brush.</p>											
7.50	Ravine, course W.; asc. 550 ft. over SW. slope.											
27.00	Spur, slopes W.; desc. 150 ft. over NW. slope.											
36.49	Proportionate point, Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for $\frac{1}{4}$ Sec. cor. of sec. 24 only, with brass cap marked											
	<div style="text-align: center;"> <table border="0"> <tr><td><math>\frac{1}{4}</math> S24</td></tr> <tr><td>1932</td></tr> </table> </div> <p style="text-align: right;">from which</p> <p>A fir, 11 ins. diam., brs. S. 68° W., 12 lks. dist., marked <math>\frac{1}{4}</math> S 24 B T.</p> <p>A fir, 10 ins. diam. brs. N. 67° W., 17 lks. dist., marked <math>\frac{1}{4}</math> S 24 B T.</p>	$\frac{1}{4}$ S24	1932									
$\frac{1}{4}$ S24												
1932												
	Continue to desc. 10 ft. over N. slope.											
37.45	Ravine, course W.; asc. 55 ft. over SW. slope.											
40.02	Mid point on the W. bdy. of sec. 19, later determined. Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for $\frac{1}{4}$ Sec. cor. of sec. 19 only, with brass cap marked											
	<div style="text-align: center;"> <table border="0"> <tr><td><math>\frac{1}{4}</math> S19</td></tr> <tr><td>1932</td></tr> </table> </div> <p style="text-align: right;">from which</p> <p>A pine, 40 ins. diam., brs. N. 65° E., 450 lks. dist., marked <math>\frac{1}{4}</math> S 19 B T.</p>	$\frac{1}{4}$ S19	1932									
$\frac{1}{4}$ S19												
1932												