

## Subdivisional Lines of T 6 N R 38 E., W.M.

Chains		Feet
	Land; rough and rocky Timber; pine, fir, spruce and tamarack & cottonwood & willow.	
	<hr/>	
	E. on a random line bet. Secs. 26 & 35.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.18	Intersect Sec. line bet. Secs. 35 and 36, 71 lks. S. of cor. for Secs. 25, 26, 35 & 36, from which cor. I run on a true line bet. Secs. 26, & 35, S. $89^{\circ} 30' W.$	
32.03	Tamarack, 10 ins. diam.	
39.58	Set post for $\frac{1}{4}$ Sec. Cor. from which A fir, 10 ins. diam. brs. N. $15^{\circ} E.$ , 76 lks. dist., A fir, 14 ins. diam. brs. S. $31^{\circ} E.$ , W 24 lks. dist.	
79.18	The cor. for secs. 26, 27, 34 & 35. Land; mountainous.	
	<hr/>	
	N. bet. Secs. 26 & 27 Var. $20^{\circ} E.$	
23.00	Ridge, falls W. and descend.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. on side hill face N.E., from which A fir, 6 ins. diam. brs. S. $20^{\circ} W.$ , 10 lks. dist., A fir, 12 ins. diam. brs. W. $30^{\circ} E.$ , 42 lks. dist.,	
48.00	Creek, 8 lks. wide, falls N.W. Ascend	
52.00	Leave timber	
80.00	Set post and mark stone, 18 x 10 x 6 ins. in mound of stone on hill side face S.W. for cor. to Secs. 22, 23, 26 & 27. Land; rough and rocky Timber; pine, fir and tamarack.	
	<hr/>	
	E. on a random line bet. Secs. 23 & 26.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.10	Intersect Sec. line, 43 lks. W. of the Cor. for Secs. 23, 24, 25 & 26, from which I run a true line N. $89^{\circ} 42' W.$ bet. Secs. 23 & 26.	
10.10	Enter timber	
19.55	Creek, 15 lks. wide, falls N.W. Ascend	