

Subdivisional Lines of T 6 N R 38 E., W.M.

Chains		Feet
40.05	Set post for $\frac{1}{4}$ Sec. Cor., from which A fir, 6 ins. diam. brs. S. 45° W., 8 lks. dist. A fir, 7 ins. diam. brs. N. 23° E., 15 lks. dist.	
45.05	Spring Branch, 1 lk. wide, falls N.E.	
49.05	Leave timber	
65.10	Summit of ridge, falls N., S. Descend	
80.10	The cor. for secs. 22, 23, 26 & 27. Land; mountainous, rough and rocky Oct. 8th, 1872.	
<hr/>		
	N. bet. Secs. 22 and 23 Var. 22° E.	
	Ascend	
19.00	Summit of ridge, falls N. 20° W., 600 ft., descend	
23.00	Enter small timber	
30.50	Gulch, spring branch, falls NW.	
34.00	Spur, of hill, fall N.W.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. on rocky hill side, face N. from which A fir, 7 ins. diam. brs. N. 42° W., 31 lks. dist. A fir, 4 ins. diam. brs. S. 82° E., 18 lks. dist.	
64.20	Prong of Mill Creek, fall W. 60° W., 12 lks. wide.	
65.00	Leave creek, ascend	
69.50	Leave timber, ascend steep rocky hill.	
80.00	Set post and marked stone in mound of earth and stone with pits for the Cor. of Secs. 14, 15, 22 & 23. Land; mountainous Timber; tamarack, pine and yew, cottonwood.	
<hr/>		
	E. on a random line bet. Secs. 14 & 23	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.68	Intersect N. and S. line, 33 lks. S. of the Cor. for Secs. 13, 14, 23 & 24, from which cor. I run S. 89° 46' W. on a true line bet. Secs. 14 & 23.	
8.58	Spr. branch, 10 lks. wide, falls, N.	
10.58	Leave timber.	