

Subdivisional Lines of T 6 N R 38 E., W.M.

Chains		Feet
39.82	Set post and mark stone in mound for $\frac{1}{4}$ Sec. Cor.	
72.35	Gulch, falls W.	
79.65	The cor. for secs. 28, 29, 32 & 33	
O ↓ To End	N. bet. Secs. 28 & 29 <div style="text-align: right;">Var. 21° E.</div>	
11.14	Enter timber	
21.30	Spring branch, 3 lks. wide, runs W.	
40.00	Set stake, $\frac{1}{4}$ Sec. Cor. from which A pine, 30 ins. diam. brs. S. 15° E. 57 lks. dist. A pine, 12 ins. diam. brs. N. 24° W., 29 lks. dist.	
70.36	Gulch, falls W. Ascend	
80.00	Set stake for the cor. to Secs. 20, 21, 28 & 29, on hill side, face E., from which A pine stump 36 ins. diam. brs. E. 12 lks. dist. Land; mountainous, poor and rocky Timber, pine, fir & tamarack.	
	E. on a random line bet. Secs. 21 & 28	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80,39	Intersect N. and S. line, 34 lks. N. of the Cor. for Secs. 21, 22, 27 & 28, from this cor. I run W. on a true line bet. Secs. 21 & 28	
23.20	Leave timber.	
40.19	Set stake for $\frac{1}{4}$ Sec. Cor.	
80.27	Pine stump, 36 in diam.	
80.39	The cor. for Secs. 28, 29, 20 & 21 Mountains, timber, pine, fir, tamarack <div style="text-align: right;">Oct. 12, 1879</div>	
	N. bet. Secs. 20 & 21 <div style="text-align: right;">Var. 19° E.</div>	
32.00	Descend steep mountain	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. on steep side hill, face W. in mound of rocks from which A fir, 6 ins. diam. brs. W. 10° E., 22 lks. dist. A fir, 3 ins. diam. brs. S. 27° E., 41 lks. dist.	