

Subdivisional Lines of T 6 N R 38 E., W.M.

Chains		Feet
50.00	Foot of bluff, Mill Creek bottom	
51.83	Shellworth's Sawmill	
55.06	Mill Creek, 40 lks. wide, flows W.	
55.46	Foot of bluff, B. Rock, 18 ft. Ascend	
60.00	Leave timber	
80.00	Set post and mark rock, 15 x 14 x 6 in mound of rock for for Cor. to Secs. 16, 17, 20 & 21	
	Mountains	
	Timber, pine, fir and tamarack.	
<hr/>		
	E. on random bet. Secs. 16 & 21	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.80	Intersect N. and S. line, 30 lks. W. of the Cor. for Secs. 15, 16, 21 & 22, from this cor. I run N. 89° 47' W. on a true line bet. Secs. 16 & 21	
26.80	Shellworth's Sawmill, brs. S. 25 chs. dist.	
39.90	Set post for $\frac{1}{4}$ Sec. Cor., from which A pine, 24 ins. in diam. brs. N. 68° E., 99 lks. dist.	
42.00	Scattering timber.	
74.30	Gulch, falls S.	
79.80	The cor. for Secs. 16, 17, 20 & 21. Land; mountains Timber, pine, fir, tamarack.	
<hr/>		
	N. bet. Secs. 16 & 17	
		Var. 20° E.
40.00	Set post in mound and pits for $\frac{1}{4}$ Sec. Cor.	
52.13	Intersect N. Bdy. state line, 16.30 chs. W. of 43 mile post I set post in mound for cor. to Fractional Secs. 16 & 17 A pine, 7 ins. diam. brs. S. 70° W., 50 lks. dist. Mountainous Good grass land.	
		Oct. 13th, 1872.