

Subdivisional Lines of T 6 N R 38 E., W.M.

Chains		Feet
	N. bet. Secs. 31 & 32	
		Var. $21\frac{1}{2}^{\circ}$ E.
27.40	Stony gulch and spring branch, 5 lks. wide, falls N.W.	
	Ascend	
34.00	Leave timber	
40.00	Set post marked B Rock, 20 x 12 x 14 in mound of rock for $\frac{1}{4}$ Sec. Cor.	
54.00	Enter timber, Descend	
80.00	Set post for the cor. to Secs. 29, 30, 31 & 32	
	A fir, 14 ins. diam. brs. N. 40° W., 37 lks. dist.	
	A fir, 12 ins. diam. brs. S. 60° E. 30 lks. dist.	
	A fir, 9 ins. diam. brs. S. 38° W., 38 lks. dist.	
	A fir, 13 ins. diam. brs. N. 22° E., 13 lks. dist.	
	Land; mountainous, rocky	
	Timber; pine, fir, tamarack.	
	<hr/>	
	E. on random line bet. Secs. 29 & 32	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.40	Intersect N. and S. 39 lks. N. of the cor. for Secs. 28, 29, 32 & 33, from which Cor. I run	
	N. $89^{\circ} 41'$ W. on a true line bet. Secs. 29 & 32	
35.40	Enter timber	
37.00	Summit of ridge, falls N. 800 ft.	
40.20	Set post for $\frac{1}{4}$ Sec. cor. from which	
	A fir, 8 ins. diam. brs. S. 10° W., 10 lks. dist.	
	A fir, 10 ins. diam. brs. N. 18° E., 10 lks. dist.	
80.40	The cor. for Secs. 29, 30, 31 & 32.	
	<hr/>	
	W. on random line bet. Secs. 30 & 31	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.60	Intersect W. Bdy., Tp., 67 lks. S. of Cor. for Secs. 25, 30, 31 & 36, from this cor. I run	
	S. $89^{\circ} 31'$ E. on true line bet. Secs. 30 & 31	
20.60	Leave timber	
30.00	Ridge falls N.E. 500 ft.	
40.30	Set post for $\frac{1}{4}$ Sec. cor. and marked stone in mound with pits	