

Subdivisional Lines of T 6 N R 38 E., W.M.

Chains		Feet
	E. on random line bet. Secs. 17 & 20	
40.00	Set post for temp. $\frac{1}{4}$ Sec. cor.	
80.15	Intersect N. and S. line, 20 lks. N. of the Cor. for Secs. 16, 17, 19 & 20, from which Cor. I run N. $89^{\circ} 51' W.$ on a true line bet. Secs. 17 & 20	
4.15	Cross spur, falls N.	
35.25	Cross gulch, falls W.	
40.07	Set post for $\frac{1}{4}$ Sec. Cor., from which A pine, 7 ins. diam., brs. S. $62\frac{1}{2}^{\circ} E.$, 61 lks. dist.,	
52.15	Ridge, falls N.	
60.15	Cross spur	
80.15	The cor. for Secs. 17, 18, 19 & 20. Good grass Timber; pine and fir Land; mountainous	
<hr/>		
	W. on random line bet. Secs. 18 & 19	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.52	Intersect W. Bdy. of Tp., 38 lks. S. of the Cor. for Secs. 13, 18, 19 & 24, from this cor. I run S. $89^{\circ} 44' E.$ on a true line bet. Secs. 18 & 19.	
40.26	Set post for $\frac{1}{4}$ Sec. Cor., from which A fir, 12 ins. diam. brs. S. $12^{\circ} W.$, 20 lks. dist. A fir, 8 ins. diam. brs. N. $10^{\circ} E.$, 40 lks. dist.	
45.52	Spring branch, 1 lks. wide, runs N.	
58.50	Mill Creek flows N.W., 60 lks. wide	
59.00	Road, Walla Walla and Saw Mill	
60.00	Leave bottom of Mill Creek	
80.52	The cor. for Secs. 17, 18, 19 & 20. Land; hilly Timber; pine and birch.	
<hr/>		
	N. bet. Secs. 17 & 18	
		Var. $21\frac{1}{4}^{\circ} E.$
1.00	Leave timber, ascend	
22.00	Sharp ridge, falls S.W. descend	