

Exterior Bdy. of T. 7 S., R. 30 E., W.M.
 As surveyed by Henry Meldrom, U.S. Deputy Surveyor,
 Under Contract No. 380.
 Dated March 19, 1881.

| Chains | | Feet |
|--------|---|------|
| | <p>E. on a random line along the N. Bdys. of Secs. 6, 5, 4, 3, 2 & 1.</p> <p style="text-align: right;">Var. 19° E.</p> <p>I set temp. $\frac{1}{4}$ Sec. and Sec. Cors., at every 40 & 80 Chs. and at 5 miles and 74 Chs. Intersect E. Bdy of T. at at the Cor. to Bdys. 6 & 7, S. Rgs. 30 & 31 E., from which Cor. I run on a true line W. on N. Bdys. of Secs. 1, 2, 3, 4, 5 & 6, as per field notes.</p> <p>W. on N. Bdy of Sec. 1</p> <p style="text-align: right;">Var. 23° 10' E.</p> | |
| 6.00 | Bed of ravine, course N.W. | |
| 40.00 | Set a basalt stone, 12 x 9 x 7 in mound of stone for $\frac{1}{4}$ Sec. Cor. | |
| 80.00 | Set a basalt stone, 14 x 14 x 7 in a mound of stone for Cor. to Secs. 1, 2, 35 & 36. | |
| | Land; hillside slopes N.W. | |
| | Soil; good 2nd rate. | |
| | Heavy Pine and Fir on E. $\frac{1}{2}$, scattering on W. $\frac{1}{2}$, | |
| | Dense plum, sarviceberry and sage undergrowth. | |
| | <hr/> | |
| | W. on N. Bdy. of Sec. 2 | |
| | Var. 26° E | |
| | Descend hill from Cor., bears N.E. and S.W. | |
| 40.00 | Set a basalt stone, 16 x 9 x 6 in a mound of stone for $\frac{1}{4}$ Sec. Cor., from which | |
| | A Pine, 30 ins. diam. brs. N. 27° W., 150 lks. dist. | |
| 44.40 | Brook, 8 lks. wide, runs N. | |
| 55.55 | N. fork of John Days River, 325 lks. wide, runs S. W. | |
| | Set flag on line and cross to opposite bank to pt. on line, measure base N. 325 Chs. where flag brs. S. 45° E., distance across 3.25 | |
| 80.00 | Set a basalt stone 18 x 15 x 10 in a mound of stone for Cor. to Secs. 2, 3, 4 & 5, on top of ridge, brs. N&S. | |
| | Land; hilly, slopes to river | |
| | Soil; 2nd rate. | |
| | Scattering Pine timber. | |