

Exterior Bdy. Lines of T. 6 S., R. 29 E. W.M.

Chains	Exterior Bdy. of T. 6 S., R. 29 E., W. M. As surveyed by Henry Meldrom, & T. W. Campbell, U. S. Dept. Surveyor Under Joint Contract, No. 380. Dated March 19, 1881.	Feet
	<p>Begin at established Cor. to Tps. 6 & 7 S., Rs. 29 & 30 E., and run, N. on E. Bdy of Sec. 36.</p> <p style="text-align: right;">Var. 19° E.</p> <p>Ascend hill from Cor.</p>	
4.50	Top of ridge and descend same.	
40.00	Set a basalt stone, 16 x 12 x 8, for $\frac{1}{4}$ Sec. Cor., from which which, A Fir, 24 ins. in diam. brs. N. 53° E., 120 lks. dist. A Fir, 20 ins. in diam. brs. N. 66° W., 14 lks. dist.	
47.00	Foot of hill, brs. N.E. and S.W.	
71.00	Creek, 20 lks. wide, runs. S.W.	
80.00	Set a post for Cor. to Secs. 25, 30, 31, & 36, from which A Fir, 27 ins. in diam. brs. N. 61° 30' W., 32 lks. dist. A Pine, 20 ins. in diam. brs. S. 29° E., 29 lks. dist. A Pine, 30 ins. in diam. brs. S. 34° W., 30 lks. dist. A Fir, 10 ins. in diam. brs. N. 31° E., 59 lks. dist.	
	Land; mountainous Soil; 2nd rate. Timber pine, fir, and juniper. Dense undergrowth on N. $\frac{1}{2}$ of laurel, cherry and Willow.	
	<p>N. on E. Bdy of Sec. 25.</p> <p style="text-align: right;">Var. 19° E.</p>	
3.00	Ascend hill, brs. N.E. and S.W.	
40.00	Set a basalt stone, 15 x 8 x 7 in mound of stone for $\frac{1}{4}$ Sec. Cor.	
47.00	Creek, 10 lks. wide, runs. S.E.	
52.00	Top of ridge, brs. N.W. and S.E.	
58.00	Brook, 3 lks. wide, runs. S.E.	
80.00	Set a basalt stone, 22 x 20 x 6 in mound of stone for Cor. to Secs. 19, 24, 25 & 30.	
	Land; broken hills	