

Exterior Lines of T. 6 S., R. 30 E., W.M.

Chains		Feet
23.00	Top of hill, brs. E. and W.	
40.00	Set a pine post for $\frac{1}{4}$ Sec. Cor., from which, A Y. pine, 40 ins. in diam. brs. N. 75° E., 66 lks. dist. A Tamarack, 16 ins. diam. brs. N. 37° W., 65 lks. dist.	
41.00	Ravine, course N.E.	
61.50	Creek, 3 lks. wide, runs S.E.	
80.00	Set a basalt stone, 12 x 8 x 8 in a mound of stone for Cor. to Secs. 13, 18, 19 & 24. Land; hilly Soil; good 2nd rate. Scattering pine and fir, undergrowth of small pine & fir timber.	
	N. on E. Bdy. of Sec. 13. Var. 20° 45' E.	
40.00	Set a Pine post for $\frac{1}{4}$ Sec. Cor., from which, A Pine, 7 ins. in diam. brs. S. 22° E., 49 lks. dist. A Pine, 7 ins. in diam. brs. S. 8° W., 51 lks. dist.	
43.00	Ravine, course E.	
51.00	Descend hill, brs. N.W. and S.E.	
69.45	Creek, 10 lks. wide, course E. Foot of hill, brs. E. and W. Ascend hill from creek	
80.00	Set a basalt stone, 20 x 12 x 3 in a mound of stone for Cor to Secs. 7, 12, 13, 18. Land; hilly, Soil; 2nd rate. Scattering Pine and Fir timber. Undergrowth of Laural and small Pine.	
	N. on E. Bdy. of Sec. 12 Var. 20° 15' E.	
4.00	Top of hill, brs. E. and W.	
15.00	Ravine, course E.	
27.69	A Pine, 40 ins. in diam. for line tree.	
40.00	Set a pine post for $\frac{1}{4}$ Sec. Cor., from which,	