

Subdivisional Lines of T. 6 S., R. 30 E., W.M.

Chains		Feet
30.44	Ravine, course S.	
39.97	Set a basalt stone, 14 x 12 x 8 in a mound of stone for ¼ Sec. Cor.	
47.94	Top of ridge, brs. N.&S.	
79.94	To Cor. to Secs. 26, 27, 34 & 35 Land; hilly Soil; 2nd rate. Scattering pine and juniper timber.	
N. bet. Secs. 26 & 27 Var. 20° E.		
40.00	Set a basalt stone, 12 x 12 x 6 in a mound of stone for ¼ Sec. Cor.	
51.00	Top of hill, brs. E. and W.	
80.00	Set a basalt stone, 18 x 15 x 6 in a mound of stone for Cor. to Secs. 22, 23, 26 & 27, from which A Pine, 30 ins. in diam. brs. N. 48° W., 33 lks. dist. A Pine, 8 ins. in diam. brs S., 79° W. 93 lks. dist.	
-	Land; hilly Soil; 2nd rate Heavy Pine timber, good bunch grass.	
E. on a random line bet. Secs. 23 & 26		
40.00	Set a temp. ¼ Sec. Cor.	
79.80	Intersect N. & S. line, 23 lks. S. of Cor. to Secs. 23, 24, 25 & 26, from which Cor. I run S. 89° 50' W. on a true line bet. Secs. 23 & 26	
.30	Spring branch, runs. S.W.	
11.50	Foot of hill, brs. N. & S.	
11.72	Creek, 8 lks. wide, runs. S.	
1180	Foot of hill	
39.90	Set a basalt stone, 16 x 9 x 7 for ¼ Sec. Cor.	
61.80	Top of hill, brs. N. and S.	
79.80	To Cor. to Secs. 22, 23, 26 & 27 Land; hilly Soil; 2nd rate.	