

## Exterior Lines, T 7 S R 32 E W M.

Chains	
42.40	Ravine, course N.W..
60.00	Top of hill brs. N.W. & S.E.
74.00	Descend hill, brs. N.W. & S.E.
80.00	Set fir post for Cor. to Secs. 2, 3, 24 & 25, from which A fir, 10 ins. diam., brs. N.74°E., 27 lks. dist. A tamarack, 4 ins. diam., brs. N.32°W., 9 lks. dist. A fir, 5 ins. diam., brs. S.70°W., 19 lks. dist. A fir, 6 ins. diam., brs. S.61°E., 25 lks. dist. Land; hilly & mountainous. Soil; 2nd rate. Heavy pine & fir timber, scattering tamarack. Dense young fir, pine & arrow wood.
	N.89°47'E. on true line on N. Bdy. of Sec. 2 Var.
31.50	Brook, 4 lks. wide, runs N.
40.00	Set yellow pine post for $\frac{1}{2}$ Sec. Cor. A yellow pine, 22 ins. diam., brs. N.75°E., 23 lks. dist. A yellow pine, 4 ins. diam., brs. S.27°E., 31 lks. dist.
57.50	Ravine, course N.
69.75	Ravine, course N.
76.00	Top of ridge, brs. N.W. & S.E.
80.00	Set fir post for Cor. to Secs. 1, 2, 35 & 36, from which A fir, 10 ins. diam., brs. N.38°E., 21 lks. dist. A fir, 8 ins. diam., brs. N.45°W., 27 lks. dist. A fir, 9 ins. diam., brs. S.72°W., 13 lks. dist., A fir, 12 ins. diam., brs. S.70°E., 20 lks. dist. Land; hillside, general slope to N. Soil; 2nd rate. Heavy pine, fir & tamarack timber. Dense young pine, fir, tamarack & mountain laurel.
	N.89°47'E. on true line on N. Bdy. Sec. 1.
8.50	Ravine, course N.10°E.
10.00	Ravine, course N.
38.35	Old mining ditch, brs. N.W.