

Exterior Lines, T 6 S R 32 E W M.

Chains

N. bet. Secs. 1 & 6.

Var. 20° E.

38.00 Brook, 3 lks. wide, course E.

40.00 Set basalt stone, 16 x 15 x 8 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which

A pine, 18 ins. diam., brs. N. 12° E., 5 lks. dist.,
marked $\frac{1}{4}$ S B T.

A pine, 12 ins. diam., brs. S. 44° W., 42 lks. dist.,
marked $\frac{1}{4}$ S B T.

65.25 Spring branch, 2 lks. wide, course N.W.

67.75 " " 3 " " " "

74.00 Intersect Standard line at 4.39 chs. E. of Cor. to Secs.
25 & 26, and set

Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground,
marked

C C T 6 S R 32 E S 1 on S.W.

T 6 S R 33 E S 6 on S.E. faces,

with 6 notches on S.E. & W. edges,

from which,

A pine, 10 ins. diam., brs. S. 63° W., 9 lks. dist.,
marked T 6 S R 32 E S 1 B T.

A pine, 30 ins. diam., brs. S. 22° E., 60 lks. dist.,
marked T 6 S R 33 E S 6 B T.

Land; mountainous.

Soil; 2nd rate.

Densely covered with forests of pine, fir, spruce, tamarack
yew and alder timber, 74.00 chs.

Thick undergrowth of small pine, fir, spruce, tamarack &
balm, 74.00 chs.

June 4, 1883.

Subdivisional Lines, T 6 S R 32 E W M.,
As surveyed by Same Dept. Surveyor,
Under same Contract & date.

I commenced at Cor. to Secs. 1, 2, 35 & 36, on S. Bdy. of
Tp., which is a post, 4 ft. long, 4 ins. sq., firmly