

Subdivisional Lines, T 6 S R 32 E W M.

Chains	
48.37	A pine, 30 ins. diam.
72.85	Brook, 4 lks. wide, course S.60°E.
80.00	To a point on W. bank of small brook, 300 ft. above $\frac{1}{4}$ Sec.
	Cor., and
	Set basalt stone, 24 x 8 x 8 ins., 18 ins. in ground, for
	Cor. to Secs. 21, 22, 27 & 28, marked with 2 notches on
	S. and 3 notches on E. edges, from which
	A pine, 10 ins. diam., brs. N.8°E., 144 lks. dist.,
	marked T 6 S R 32 E S 22 B T.
	A pine, 12 ins. diam., brs. S.15°E., 104 lks. dist.,
	marked T 6 S R 32 E S 27 B T.
	A pine, 12 ins. diam., brs. S.11°W., 27 lks. dist.,
	marked T 6 S R 32 E S 28 B.T.
	A pine, 8 ins. diam., brs. N.25°W., 28 lks. dist.,
	marked T 6 S R 32 E S 21 B T.
	Land; mountainous.
	Soil; 2nd rate.
	Densely covered with forests of pine timber, 80 chs.
	Thick undergrowth of small pine, 80 chs.
<hr/>	
	E. on random line bet. Secs. 22 & 27.
	Var. 20°E.
0.15	Brook, 6 lks. wide, course S.
	Thence descend over rolling ground.
25.00	Trail to Texas Bar, and ascend gently.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
	Descend abruptly.
45.25	Ravine, course S., foot of hill.
46.00	Ascend abruptly.
67.00	Top of ridge, course N. & S. and descend.
71.00	Brook, 5 lks. wide, course S.
	Ascend.
80.00	Intersect N. & S. line at Cor. to Secs. 22, 23, 26 & 27.
	Thence I run
	W. on true line bet. Secs. 22 & 27.
	With same Var.