

Subdivisional Lines, T 6 S R 32 E W M.

Chains

5 notches on S. and 3 notches on E. edges, from which

A pine, 8 ins. diam., brs. N.26°W., 12 lks. dist.,
marked T 6 S R 32 E S 4 B T.

A pine, 12 ins. diam., brs. N.15°E., 26 lks. dist.,
marked T 6 S R 32 E S 3 B T.

No trees within limits in Secs. 9 & 10; dug pits, 18 x
18 x 12 ins. in each Sec., 5½ ft. dist. and raised
mound of earth, 2 ft. high, 4½ ft. base alongside.

Land; gently rolling.

Soil; 2nd rate.

Densely covered with forests of pine, fir & tamarack tim-
ber, 80 chs.

E. on random line bet. Secs. 3 & 10.

Var. 19°50'E.

Over gently rolling ground through dense forest.

40.00 Set temp. ¼ Sec. Cor.

79.76 Intersect N. & S. line, 15 lks. N. of Cor. to Secs. 2, 3,
10 & 11.

Thence I run

N.89°54'W. on true line bet. Secs. 3 & 10.

With same Var.

39.88 Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground,
for ¼ Sec. Cor., marked ¼ S on N. face, from which
A fir, 30 ins. diam., brs. S.57°W., 31 lks. dist.,
marked ¼ S B T.

A pine, 13 ins. diam., brs. N.68°E., 35 lks. dist.,
marked ¼ S B T.

79.76 The Cor. to Secs. 3, 4, 9 & 10.

Land; gently rolling.

Soil; 2nd rate.

Densely covered with forests of pine, fir & tamarack tim-
ber, 79.76 chs.

Thick undergrowth of small pine & fir, 79.76 chs.