

Exterior Lines, T.6 S., R.33 E., W. M.

Chains

marked T 6 S R 33 E S 32 B T.

Land; rolling.

Soil; 3rd rate.

Densely covered with forests of pine & fir, 80 chs.

Thick undergrowth of pine & fir, 80 chs.

S.89°46'E. on true line bet. Secs. 4 & 33.

Var.20°E.

Ascend.

5.50 Ravine, course S.

40.00 A point, 200 ft. above last Sec. Cor.

Set granite stone, 18 x 18 x 11 ins., 12 ins. in ground,

for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which

A pine, 20 ins. diam., brs. S.71°E., 94 lks. dist.,

marked $\frac{1}{4}$ S B T.

A pine, 10 ins. diam., brs. N.88°W., 70 lks. dist.,

marked $\frac{1}{4}$ S B T.

57.50 Brook, 3 lks. wide, runs S.

Ascend.

80.00 A point on side of mountain, 80 ft. above creek.

Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for

Cor. to Secs. 3, 4, 33 & 34, marked

T 6 S S 34 on N.E.

R 33 E S 3 on S.E.

T 7 S S 4 on S.W.

S 33 on N.W. faces, with

3 notches on E. & W. edges

from which

A fir, 20 ins. diam., brs. N.81°E., 38 lks. dist.,

marked T 6 S R 33 E S 34 B T.

A fir, 10 ins. diam., brs. S.9°E., 102 lks. dist.,

marked T 7 S R 33 E S 3 B T.

A tamarack, 30 ins. diam., brs. S.17°W., 80 lks. dist.,

marked T 7 S R 33 E S 4 B T.

A pine, 36 ins. diam., brs. N.10°W., 62 lks. dist.,

marked T 6 S R 33 E S 33 B T.